NOTES:
1. UTILITIES REPRESENTED ON THIS PLAN ARE BASED ON VISUAL SURVEY OF MARKINGS AND FACILITIES IN THE FIELD. THE CITY OF NORMANDY DOES NOT WARRANT THE LOCATIONS OF THESE FACILITIES AS PRECISE. IT IS POSSIBLE THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS PRESENTLY NOT KNOWN OR SHOWN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXISTENCE AND PRECISE LOCATION OF ALL FACILITIES AND TO AVOID DAMAGE.
2. REFER TO EXISTING FEATURES & REMOVALS PLAN FOR REMOVAL OF EXISTING IMPROVEMENTS.
3. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL FOR IMPROVEMENTS TO INCLUDE, BUT NOT LIMITED TO:
   - IRRIGATION PLAN
   - ELECTRICAL / LIGHTING PLAN
   - TEAR DROP PARK SIGN
   - PLANTER WALL

   SEE JOB SPECIAL PROVISIONS FOR DESIGN REQUIREMENTS.
4. SEE JOB SPECIAL PROVISIONS FOR BENCH, TRASH RECEPTACLE, GAZEBO, AND EVENT PLATFORM WITH ARBOR STRUCTURE DETAILS.
5. REFER TO PLANTING PLAN AND JOB SPECIAL PROVISIONS FOR PLANTING DETAILS.
6. ALL CONCRETE PADS AND WALKWAYS SHALL HAVE EXPOSED MERAMEC AGGREGATE.
7. CONTRACTOR TO PROVIDE CONDUIT AND ELECTRICAL CONDUCTORS TO POWER ALL LIGHTING FIXTURES AND RECEPTACLES. SEE JOB SPECIAL PROVISIONS.

OVERHEAD ELECTRIC

MOUNT NEW ELECTIC METER ON EXISTING UTILITY POLE

INSTALL PAD MOUNTED LIGHTING CONTROLLER AT BASE OF EXISTING UTILITY POLE

EXPOSED MERAMEC AGGREGATE CONCRETE EVENT PLATFORM WITH ARBOR STRUCTURE. PROVIDE ELECTRICAL RECEPTACLES SEE DESIGN DRAWING & REFER TO JOB SPECIAL PROVISIONS FOR DETAILS

PLANTED AREAS "A" PER PLANTING PLAN

REMOVE EXISTING TOP 6" OF GROUND SURFACE. REPLACE WITH TOP SOIL AND SOD PER SPECIFICATIONS.

OPEN CELLED GRAVEL PAVEMENT WALKWAY WITH FLAGSTONE STEPPING STONES SEE JOB SPECIAL PROVISIONS FOR DETAILS

ENTIRE PARK TO BE IRRIGATED SEE JOB SPECIAL PROVISIONS FOR ZONING AND OTHER IRRIGATION REQUIREMENTS

EXISTING GAS LINE

TRASH RECEPTACLE ON EXPOSED MERAMEC AGG. CONCRETE PAD (TYP)

CONCRETE CURB RAMP WITH FULL WIDTH TRUNCATED DOMES (TYP)

LIGHTED BOLLARD (TYP) SEE JOB SPECIAL PROVISIONS

CONCRETE WALKWAY WITH EXPOSED MERAMEC AGGREGATE (TYP)

EXISTING CURB (TYP)

GAZEBO WITH EXPOSED MERAMEC AGGREGATE CONCRETE PAD. PROVIDE INTERIOR LIGHT & NEARBY ELECTRICAL RECEPTACLE SEE JOB SPECIAL PROVISIONS

PLANTED AREA "B" PER PLANTING PLAN (TYP)

GROUND MOUNTED UPLIGHT (TYP) SEE JOB SPECIAL PROVISIONS

SUSPECTED LOCATION OF WATER MAIN

BENCH ON EXPOSED MERAMEC AGG. CONCRETE PAD (TYP)

STREET LIGHT (TYP) SEE JOB SPECIAL PROVISIONS

PLANTED AREA "C" PER PLANTING PLAN

WATER MAIN TAP FOR IRRIGATION SYSTEM

WATER VALVE

IRRIGATION CONTROLS & BACKFLOW PREVENTER

TEAR DROP PARK SIGN SEE JOB SPECIAL PROVISIONS

GROUND MOUNTED LIGHT FOR PARK SIGN SEE JOB SPECIAL PROVISIONS

CONCRETE PLANTER WALL WITH NATURAL STONE TOP

SUSPECTED LOCATION OF GAS LINE

FOR INFORMATION ONLY

DATE PREPARED	9/17/2010
ROUTE	STATE
DISTRICT	SHEET NO.
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DATE	DESCRIPTION

PLAN OF IMPROVEMENTS
TEARDROP PARK
CITY OF NORMANDY